

Norway

SLEIPNER

Volve F

F-11

15/9-F-11 A

Plan: 15/9-F-11 A NWest PIL DG3 rev0

Standard Survey Report

11 april, 2018

Statoil

Survey Report

Company:	Norway	Local Co-ordinate Reference:	Site Volve F
Project:	SLEIPNER	TVD Reference:	MI @ 54.90m (MI)
Site:	Volve F	MD Reference:	MI @ 54.90m (MI)
Well:	F-11	North Reference:	Grid
Wellbore:	15/9-F-11 A	Survey Calculation Method:	Minimum Curvature
Design:	15/9-F-11 A NWest PIL DG3 rev0	Database:	Production EDM P246N

Project	SLEIPNER, Norway		
Map System:	Universal Transverse Mercator	System Datum:	Mean Sea Level
Geo Datum:	European 1950 - Mean		Using Well Reference Point
Map Zone:	Zone 31N (0 E to 6 E)		Using geodetic scale factor

Site	Volve F, 15/9		
Site Position:		Northing:	6,478,563.53 m
From:	Map	Easting:	435,050.02 m
Position Uncertainty:	0.00 m	Slot Radius:	13.200 in
		Latitude:	58° 26' 29.8068 N
		Longitude:	1° 53' 14.9285 E
		Grid Convergence:	-0.95 °

Well	F-11		
Well Position	+N/-S	4.65 m	Northing:
	+E/-W	-0.93 m	Easting:
Position Uncertainty	0.00 m		Wellhead Depth:
			91.00 m
			Latitude:
			58° 26' 29.9566 N
			Longitude:
			1° 53' 14.8667 E
			Water Depth:
			91.00 m

Wellbore	15/9-F-11 A				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	MNETICREFERENCE	31.12.2010	-1.67	71.63	50,439

Design	15/9-F-11 A NWest PIL DG3 rev0				
Audit Notes:					
Version:	Phase:	PLAN	Tie On Depth:	2,570.00	
Vertical Section:	Depth From (TVD) (m)	+N/-S (m)	+E/-W (m)	Direction (°)	
	145.90	4.65	-0.93	22.19	

Survey Tool Program	Date	05.08.2014			
From (m)	To (m)	Survey (Wellbore)	Tool Name	Description	
2,570.00	3,713.91	15/9-F-11 A NWest PIL DG3 rev0 (15/9-F-			

Planned Survey										
Measured Depth (m)	Inclination (°)	Azimuth (°)	Vertical Depth (m)	+N/-S (m)	+E/-W (m)	Vertical Section (m)	Dogleg Rate (°/30m)	Build Rate (°/30m)	Turn Rate (°/30m)	
2,570.00	36.93	68.78	2,440.31	39.36	-348.15	-99.02	0.000	0.000	0.000	
2,570.68	36.98	68.81	2,440.85	39.50	-347.77	-98.74	2.322	2.162	1.412	
2,580.68	36.98	68.81	2,448.84	41.68	-342.16	-94.61	0.000	0.000	0.000	
2,640.68	34.32	59.57	2,497.63	56.78	-310.72	-68.75	3.000	-1.330	-4.620	
3,069.95	76.97	40.79	2,735.68	288.45	-56.51	241.78	3.150	2.981	-1.312	
3,167.78	76.97	40.79	2,757.73	360.61	5.76	332.11	0.000	0.000	0.000	
3,513.29	40.14	39.47	2,934.90	581.68	193.00	607.53	3.200	-3.199	-0.115	
3,641.35	40.14	39.47	3,032.80	645.40	245.47	686.35	0.000	0.000	0.000	
3,713.91	40.14	39.47	3,088.28	681.51	275.20	731.02	0.000	0.000	0.000	

Statoil

Survey Report

Company:	Norway	Local Co-ordinate Reference:	Site Volve F
Project:	SLEIPNER	TVD Reference:	MI @ 54.90m (MI)
Site:	Volve F	MD Reference:	MI @ 54.90m (MI)
Well:	F-11	North Reference:	Grid
Wellbore:	15/9-F-11 A	Survey Calculation Method:	Minimum Curvature
Design:	15/9-F-11 A NWest PIL DG3 rev0	Database:	Production EDM P246N

Design Targets									
Target Name	Dip Angle	Dip Dir.	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
- hit/miss target	(°)	(°)	(m)	(m)	(m)	(m)	(m)		
- Shape									
F-15 E NW Pilot Base H	0.00	360.00	3,032.80	645.40	245.46	6,479,208.70	435,295.40	58° 26' 50.7936 N	1° 53' 29.4005 E
- plan hits target center									
- Point									

Casing Points					
Measured Depth	Vertical Depth	Name		Casing Diameter	Hole Diameter
(m)	(m)			(in)	(in)
2,570.68	2,440.85	14"		14.000	17.500

Checked By: _____ Approved By: _____ Date: _____