

Norway

SLEIPNER

Volve F

F-12

F-12

Plan: F12 Rev0.11 CC 240707

Standard Survey Report

11 april, 2018

Statoil

Survey Report

Company:	Norway	Local Co-ordinate Reference:	Site Volve F
Project:	SLEIPNER	TVD Reference:	Rotary Table @ 54.90m (Actual RTE as installed)
Site:	Volve F	MD Reference:	Rotary Table @ 54.90m (Actual RTE as installed)
Well:	F-12	North Reference:	Grid
Wellbore:	F-12	Survey Calculation Method:	Minimum Curvature
Design:	F12 Rev0.11 CC 240707	Database:	Production EDM P246N

Project	SLEIPNER, Norway		
Map System:	Universal Transverse Mercator	System Datum:	Mean Sea Level
Geo Datum:	European 1950 - Mean		Using Well Reference Point
Map Zone:	Zone 31N (0 E to 6 E)		Using geodetic scale factor

Site		Volve F, 15/9			
Site Position:		Northing:	6,478,563.53 m	Latitude:	58° 26' 29.8068 N
From:	Map	Easting:	435,050.02 m	Longitude:	1° 53' 14.9285 E
Position Uncertainty:	0.00 m	Slot Radius:	13.200 in	Grid Convergence:	-0.95 °

Well	F-12					
Well Position	+N/-S	2.70 m	Northing:	6,478,566.22 m	Latitude:	58° 26' 29.8941 N
	+E/-W	0.19 m	Easting:	435,050.21 m	Longitude:	1° 53' 14.9374 E
Position Uncertainty		0.00 m	Wellhead Depth:	91.00 m	Water Depth:	91.00 m

Wellbore	F-12				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	MAGNETICREFERENCE	01.03.2007	-2.34	71.63	50,321

Design	F12 Rev0.11 CC 240707				
Audit Notes:					
Version:	Phase:	PLAN	Tie On Depth:	145.90	
Vertical Section:	Depth From (TVD) (m)	+N/-S (m)	+E/-W (m)	Direction (°)	
	145.90	2.70	0.19	144.90	

Survey Tool Program	Date	31.05.2010			
From (m)	To (m)	Survey (Wellbore)	Tool Name	Description	
145.90	3,441.29	F12 Rev0.11 CC 240707 (F-12)	Magnetic, std, mag-corr	Magnetic Tools (MWD, EMS)	

Planned Survey									
Measured Depth (m)	Inclination (°)	Azimuth (°)	Vertical Depth (m)	+N/-S (m)	+E/-W (m)	Vertical Section (m)	Dogleg Rate (°/30m)	Build Rate (°/30m)	Turn Rate (°/30m)
145.90	0.00	0.00	145.90	2.70	0.19	0.00	0.000	0.000	0.000
284.00	0.00	45.00	284.00	2.70	0.19	0.00	0.000	0.000	0.000
524.00	8.00	45.00	523.22	14.53	12.02	-2.87	1.000	1.000	0.000
877.42	16.51	258.94	872.57	22.39	-20.33	-27.92	2.000	0.722	-12.398
1,066.02	16.51	258.94	1,053.40	12.11	-72.94	-49.75	0.000	0.000	0.000
1,131.49	20.64	254.49	1,115.45	7.24	-93.19	-57.42	2.000	1.892	-2.039
1,935.32	20.64	254.49	1,867.68	-68.53	-366.22	-152.44	0.000	0.000	0.000
3,017.32	53.78	104.53	2,823.32	-254.23	-89.99	158.33	2.000	0.919	-4.158
3,441.29	53.78	104.53	3,073.84	-340.04	241.11	418.94	0.000	0.000	0.000

Statoil

Survey Report

Company:	Norway	Local Co-ordinate Reference:	Site Volve F
Project:	SLEIPNER	TVD Reference:	Rotary Table @ 54.90m (Actual RTE as installed)
Site:	Volve F	MD Reference:	Rotary Table @ 54.90m (Actual RTE as installed)
Well:	F-12	North Reference:	Grid
Wellbore:	F-12	Survey Calculation Method:	Minimum Curvature
Design:	F12 Rev0.11 CC 240707	Database:	Production EDM P246N

Design Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (m)	+N/-S (m)	+E/-W (m)	Northing (m)	Easting (m)	Latitude	Longitude
Start Tangent - plan misses target center by 2.80m at 3013.68m MD (2821.17 TVD, -253.49 N, -92.83 E) - Point	0.00	0.00	2,821.28	-250.70	-93.03	6,478,312.91	434,957.03	58° 26' 21.6557 N	1° 53' 9.4514 E
Volve P60 50deg Topp - plan misses target center by 85.77m at 3017.32m MD (2823.32 TVD, -254.23 N, -89.99 E) - Point	0.00	0.00	2,874.90	-268.58	-22.99	6,478,295.04	435,027.04	58° 26' 21.1155 N	1° 53' 13.7856 E
Volve P61 50deg Bunn - plan misses target center by 1.92m at 3274.67m MD (2975.39 TVD, -306.31 N, 110.99 E) - Point	0.00	0.00	2,976.90	-305.63	110.02	6,478,258.00	435,160.00	58° 26' 19.9893 N	1° 53' 22.0199 E

Checked By: _____	Approved By: _____	Date: _____
-------------------	--------------------	-------------