

Norway

SLEIPNER

Volve F

F-8

F-8

Plan: F8 Volve Sør Prod DRAFT NewRigCoords 220607

Standard Survey Report

11 april, 2018

Statoil

Survey Report

Company:	Norway	Local Co-ordinate Reference:	Site Volve F
Project:	SLEIPNER	TVD Reference:	Maersk Inspirer @ 54.00m
Site:	Volve F	MD Reference:	Maersk Inspirer @ 54.00m
Well:	F-8	North Reference:	Grid
Wellbore:	F-8	Survey Calculation Method:	Minimum Curvature
Design:	F8 Volve Sør Prod DRAFT NewRigCoords 220607	Database:	Production EDM P246N

Project	SLEIPNER, Norway		
Map System:	Universal Transverse Mercator	System Datum:	Mean Sea Level
Geo Datum:	European 1950 - Mean		Using Well Reference Point
Map Zone:	Zone 31N (0 E to 6 E)		Using geodetic scale factor

Site	Volve F, 15/9			
Site Position:		Northing:	6,478,563.53 m	Latitude: 58° 26' 29.8068 N
From: Map		Easting:	435,050.02 m	Longitude: 1° 53' 14.9285 E
Position Uncertainty:	0.00 m	Slot Radius:	13.200 in	Grid Convergence: -0.95 °

Well	F-8			
Well Position	+N/-S	0.00 m	Northing:	6,478,563.53 m
	+E/-W	0.00 m	Easting:	435,050.02 m
Position Uncertainty	0.00 m		Wellhead Depth:	91.00 m
			Water Depth:	91.00 m

Wellbore	F-8				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	NETICREFERENCE	26.10.2005	-2.54	71.62	50,282

Design	F8 Volve Sør Prod DRAFT NewRigCoords 220607			
Audit Notes:				
Version:	Phase:	PLAN	Tie On Depth:	145.00
Vertical Section:	Depth From (TVD) (m)	+N/-S (m)	+E/-W (m)	Direction (°)
	145.00	0.00	0.00	203.01

Survey Tool Program	Date	31.05.2010		
From (m)	To (m)	Survey (Wellbore)	Tool Name	Description
145.00	254.00	F8 Volve Sør Prod DRAFT NewRigCoords	NOTuse_Wellbore Surveyor,	Gyro Tool from GD
254.00	3,889.49	F8 Volve Sør Prod DRAFT NewRigCoords	Magnetic, std, non-mag	Magnetic Tools (MWD, EMS)

Planned Survey										
Measured Depth (m)	Inclination (°)	Azimuth (°)	Vertical Depth (m)	+N/-S (m)	+E/-W (m)	Vertical Section (m)	Dogleg Rate (°/30m)	Build Rate (°/30m)	Turn Rate (°/30m)	
145.00	0.00	0.00	145.00	0.00	0.00	0.00	0.000	0.000	0.000	
254.00	0.00	0.00	254.00	0.00	0.00	0.00	0.000	0.000	0.000	
532.00	0.00	0.00	532.00	0.00	0.00	0.00	0.000	0.000	0.000	
1,162.06	42.00	191.48	1,107.12	-216.37	-43.94	216.33	2.000	2.000	0.000	
3,024.96	42.00	191.48	2,491.44	-1,438.06	-292.00	1,437.80	0.000	0.000	0.000	
3,889.49	55.00	270.00	3,114.00	-1,748.13	-742.28	1,899.20	2.000	0.451	2.725	

Statoil

Survey Report

Company:	Norway	Local Co-ordinate Reference:	Site Volve F
Project:	SLEIPNER	TVD Reference:	Maersk Inspirer @ 54.00m
Site:	Volve F	MD Reference:	Maersk Inspirer @ 54.00m
Well:	F-8	North Reference:	Grid
Wellbore:	F-8	Survey Calculation Method:	Minimum Curvature
Design:	F8 Volve Sør Prod DRAFT NewRigCoords 220607	Database:	Production EDM P246N

Design Targets									
Target Name									
- hit/miss target	Dip Angle	Dip Dir.	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
- Shape	(°)	(°)	(m)	(m)	(m)	(m)	(m)		
Volve P50 Topp	0.00	0.94	2,858.10	96.51	266.07	6,478,660.00	435,316.00	58° 26' 33.0675 N	1° 53' 31.2283 E
- plan misses target center by 1465.46m at 2216.75m MD (1890.86 TVD, -908.03 N, -184.38 E)									
- Point									
Volve P70 Topp	0.00	0.95	2,921.00	-537.71	-29.13	6,478,026.00	435,020.90	58° 26' 12.4154 N	1° 53' 13.6817 E
- plan misses target center by 985.12m at 2718.72m MD (2263.87 TVD, -1237.22 N, -251.22 E)									
- Point									
Volve I20	0.00	0.94	3,000.00	-765.79	665.21	6,477,798.00	435,715.00	58° 26' 5.4145 N	1° 53' 56.6978 E
- plan misses target center by 1261.18m at 2834.53m MD (2349.94 TVD, -1313.18 N, -266.64 E)									
- Point									
Volve P51 Bunn	0.00	0.94	3,015.12	578.68	423.63	6,479,142.00	435,473.50	58° 26' 48.7323 N	1° 53' 40.4499 E
- plan misses target center by 1948.16m at 1996.24m MD (1727.00 TVD, -763.43 N, -155.02 E)									
- Point									
Volve I10 Topp	0.00	0.96	3,094.00	399.62	-597.23	6,478,963.00	434,453.00	58° 26' 42.3993 N	1° 52' 37.7106 E
- plan misses target center by 1821.97m at 2308.23m MD (1958.84 TVD, -968.03 N, -196.56 E)									
- Point									
North Producer AMAP 2l	0.00	0.00	3,109.00	532.66	894.29	6,479,096.00	435,944.00	58° 26' 47.4945 N	1° 54' 9.5072 E
- plan misses target center by 2165.51m at 2033.51m MD (1754.70 TVD, -787.87 N, -159.98 E)									
- Point									
Volve Sør 120107	0.00	0.00	3,114.00	-1,748.13	-742.28	6,476,816.00	434,308.00	58° 25' 32.9179 N	1° 52' 30.9848 E
- plan hits target center									
- Point									
Volve P71 Bunn	0.00	0.97	3,122.80	-468.69	-1,446.72	6,478,095.00	433,603.80	58° 26' 13.8794 N	1° 51' 46.2574 E
- plan misses target center by 1495.92m at 3796.23m MD (3058.00 TVD, -1744.21 N, -667.86 E)									
- Point									
Volve I21 Bunn	0.00	0.94	3,131.00	-765.79	665.21	6,477,798.00	435,715.00	58° 26' 5.4145 N	1° 53' 56.6978 E
- plan misses target center by 1329.88m at 2931.88m MD (2422.28 TVD, -1377.02 N, -279.61 E)									
- Point									
Volve I30 Topp	0.00	0.93	3,132.93	-121.57	1,441.38	6,478,442.00	436,490.90	58° 26' 26.6407 N	1° 54' 43.8814 E
- plan misses target center by 2183.57m at 2407.48m MD (2032.59 TVD, -1033.12 N, -209.78 E)									
- Point									
Volve I31 Bunn	0.00	0.93	3,238.44	-121.57	1,441.38	6,478,442.00	436,490.90	58° 26' 26.6407 N	1° 54' 43.8814 E
- plan misses target center by 2237.22m at 2485.88m MD (2090.86 TVD, -1084.53 N, -220.22 E)									
- Point									

Casing Points					
Measured Depth (m)	Vertical Depth (m)	Name	Casing Diameter (in)	Hole Diameter (in)	
254.00	254.00	30"	30.000	36.000	

Checked By: _____	Approved By: _____	Date: _____
-------------------	--------------------	-------------